



ABN 50 006 673 470

Test Certificate

Final

Lot 242 Russell Road East,
Munster WA 6166
PO Box 38, Hamilton Hill WA 6963
T: +61 8 9411 1000
F: +61 8 9411 1150
www.cockburncement.com.au

Product Certified: Ground Granulated Blast Furnace Slag
Test Certificate Number: 170486
Despatched From: Cockburn Cement, Kwinana Plant, WA
Sample Code: B063084
Sample Date: 1/04/2018

| Nominal Blend | Requirements | Result |
|-------------------------------------------|--------------|--------|
| Ground Granulated Iron Blast-Furnace Slag | | >95 % |
| Calcium Sulphate | | <5 % |

| Reportable Property | Test Method | Requirements of AS3582.2 | Result |
|---------------------------------------------|-------------|--------------------------|--------------|
| Alumina (Al ₂ O ₃) | AS2350.2 | Max 18.0 % | 11.8 % |
| Total Iron (FeO) | AS2350.2 | N/R | 1.2 % |
| Magnesia (MgO) | AS2350.2 | Max 15.0 % | 5.8 % |
| Total Alkali (Na ₂ O Equivalent) | AS2350.2 | N/R | 0.4 % |
| Manganese (MnO) | ASTM C114 | N/R | 0.2 % |
| Sulfate (as SO ₃) content | AS3583.8 | N/R | 1.4 % |
| Sulfide Sulfur (S) | AS3583.7 | Max 1.5 % | 0.9 % |
| Chloride Ion Content | AS3583.13 | Max 0.1 % | 0.009 % |
| Loss on Ignition | AS3583.3 | N/R | -0.4 % |
| Insoluble Residue | AS3583.14 | N/R | 0.6 % |
| 45 µm Residue | AS3583.1 | N/R | 98 % passing |
| Relative Density | AS3583.5 | N/R | 2.87 |
| Relative Water Requirement | AS3583.6 | N/R | 103 % |
| Strength Index | AS3583.6 | N/R | 95 % |

Other Properties

| | | | |
|------------------|----------|-----|------------------------|
| SiO ₂ | AS2350.2 | N/R | 33.0 % |
| CaO | AS2350.2 | N/R | 43.3 % |
| Fineness Index | AS2350.8 | N/R | 450 m ² /kg |

This document shall not be reproduced except in full.

REMARKS

These test results apply specifically to the above designated sample as received at the Adelaide Brighton Cement Birkenhead Laboratory (Accredited number: 252), 62 Elder Rd Birkenhead SA 5015.

For Relative Water and Strength Index testing the reference control used is Birkenhead GP code B063080.

This despatch grab sample complies to the requirements of AS3582.2:2016, Ground Granulated Blast Furnace Slag.

N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Approved Signatory

F. Pope

Issue Date: 12/06/2018