

## **Cement Test Certificate**

Lot 242 Russell Road East, Munster WA 6166 PO Box 38, Hamilton Hill WA 6963 T: +61 8 9411 1000

F: +61 8 9411 1150

Final ABN 50 006 673 470

**Product Certified:** 

Type GP Coarse General Purpose Cement

**Test Certificate Number:** 200485

**Produced At:** Cockburn Cement, Kwinana Plant, WA

Sample Code: B07c097 Sample Date: 6/10/2020

| Nominal Blend                             | Requirements | Result |
|---|--------------|--------|
| Clinker                                   |              | >95 %  |
| Ground Granulated Iron Blast-Furnace Slag |              | Nil    |
| Mineral Addition                          | Max 7.5 %    | Nil    |
| Calcium Sulphate                          |              | 5%     |
| Minor Additional Constituents             | Max 5 %      | Nil    |

| Reportable Property                           | Test Method   | Requirements of | Result    |
|---|---------------|-----------------|-----------|
|   | rest iviethou | AS3972          |           |
| 3 Day Strength                                | AS2350.11     | N/R             | 41.4 MPa  |
| 7 Day Strength                                | AS2350.11     | Min 35.0 MPa    | 51.0 MPa  |
| 28 Day Strength                               | AS2350.11     | Min 45.0 MPa    | 61.0 MPa  |
| Initial Set Time                              | AS2350.4      | Min 45 min      | 90 min    |
| Final Set Time                                | AS2350.4      | Max 360 min     | 165 min   |
| Soundness                                     | AS2350.5      | Max 5 mm        | 1 mm      |
| Sulfuric Anhydride content (SO <sub>3</sub> ) | AS2350.2      | Max 3.5 %       | 3.1 %     |
| Chloride Ion                                  | BH-TM-0507    | Max 0.10 %      | 0.019 %   |
| Other Properties                              |               |                 |           |
| SiO <sub>2</sub>                              | AS2350.2      | N/R             | 20.4 %    |
| $Al_2O_3$                                     | AS2350.2      | N/R             | 5.5 %     |
| $Fe_2O_3$                                     | AS2350.2      | N/R             | 2.9 %     |
| CaO   | AS2350.2      | N/R             | 64.4 %    |
| MgO   | AS2350.2      | N/R             | 1.3 %     |
| Na <sub>2</sub> O Equivalent                  | AS2350.2      | N/R             | 0.6 %     |
| Loss on Ignition                              | AS2350.2      | N/R             | 1.2 %     |
| Fineness Index                                | AS2350.8      | N/R             | 350 m²/kg |
| Normal Consistency                            | AS2350.3      | N/R             | 29.3 %    |

This document shall not be reproduced except in full.

## **REMARKS**

These test result apply specifically to the sample as received at the Adelaide Brighton Cement Birkenhead Laboratory (Accreditation number: 252), 62 Elder Rd Birkenhead SA 5015.

This despatch grab sample complies to the requirements of AS3972:2010, Type GP Cement. N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

**Approved Signatory** M. Wythe

Issue Date: 30/11/2020