

Cement Test Certificate

Final

Product Certified: Type HE High Early Strength Cement (White)
Test Certificate Number: 240386
Customer: Cockburn Cement, Kwinana Plant, WA
Sample Code: B0aa226
Sample Date: 10/05/2024

Nominal Blend	Requirements	Result
Clinker		>85 %
Ground Granulated Iron Blast-Furnace Slag		Nil
Mineral Addition	Max 7.5 %	<7.5 %
Calcium Sulphate		4-8 %
Minor Additional Constituents	Max 5 %	<5%

Reportable Property	Test Method	Requirements of AS3972	Result
3 Day Strength	AS/NZS2350.11	Min 25.0 MPa	41.4 MPa
7 Day Strength	AS/NZS2350.11	Min 40.0 MPa	48.1 MPa
28 Day Strength	AS/NZS2350.11	N/R	58.8 MPa
Initial Set Time	AS/NZS2350.4	Min 45 min	165 min
Final Set Time	AS/NZS2350.4	Max 360 min	210 min
Soundness	AS/NZS2350.5	Max 5 mm	1 mm
Sulfuric Anhydride content (SO ₃)	AS2350.2	Max 3.5 %	3.3 %
Chloride Ion	BH-TM-0507	Max 0.10 %	0.026 %

Other Properties

SiO ₂	AS2350.2	N/R	21.7 %
Al ₂ O ₃	AS2350.2	N/R	3.7 %
Fe ₂ O ₃	AS2350.2	N/R	0.2 %
CaO	AS2350.2	N/R	64.7 %
MgO	AS2350.2	N/R	1.4 %
Na ₂ O Equivalent	AS2350.2	N/R	0.6 %
Loss on Ignition	AS2350.2	N/R	4.1 %
Fineness Index	AS/NZS2350.8	N/R	395 m ² /kg
Normal Consistency	AS/NZS2350.3	N/R	28.9 %
Brightness (L)*	MU-TM-2614	N/R	91

This document shall not be reproduced except in full.

REMARKS

These test result apply specifically to the sample as received at the Adbri Cement Birkenhead Laboratory (Accreditation number: 252), 62 Elder Rd Birkenhead SA 5015.


This despatch grab sample complies to the requirements of AS3972:2010, Type HE Cement.

*NATA accreditation 252 does not cover the performance of this service.

N/R = No Requirement



Accredited for compliance with ISO/IEC
17025 - Testing.



Approved Signatory

M. Wythe

Issue Date: 1/08/2024